



A401 EQUIPMENT PLAN
 SCALE: 3/16"=1'-0"
 0 2 4

EQUIPMENT PLAN NOTES

1. ALL SCHEDULED KITCHEN & BAR FOOD SERVICE EQUIPMENT & ALL FURNITURE & FURNISHINGS WILL BE SUPPLIED F.O.B. JOB SITE BY OWNER, EXCEPT MILLWORK. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING UTILITY PROVISION, & SOFT CONNECTIONS SHALL BE BY OWNER. CONTRACTOR TO CONFIRM & COORDINATE ALL FOOD SERVICE EQUIPMENT UTILITY CONNECTIONS W/ OWNER'S KITCHEN EQUIPMENT CONSULTANT. OWNER SHALL PERFORM FINAL EQUIPMENT PLACEMENT & CONNECTIONS EXCEPT AS NOTED IN SCHEDULE.
2. OWNER TO SUPPLY (1) WALL-MOUNTED SOAP DISPENSER & (1) WALL-MOUNTED PAPER TOWEL DISPENSER AT EACH EMPLOYEE HAND SINK TO BE INSTALLED BY CONTRACTOR. CONTRACTOR TO INSTALL SIGN NOTIFYING "FOOD EMPLOYEES TO WASH THEIR HANDS" AT HAND SINKS.
3. G.C. SHALL PROVIDE SOLID FRT WOOD OR SHEET METAL BLOCKING / BACKING IN ALL WALLS AS REQUIRED FOR INSTALLATION OF ALL WALL-MOUNTED ACCESSORIES AND EQUIPMENT, REGARDLESS OF WHETHER ITEM IS PROVIDED BY TENANT OR G.C.
4. CONTRACTOR TO PROVIDE DUMPSTER FOR THE DISPOSAL AND REMOVAL OF ALL BAR EQUIPMENT GARBAGE AND PACKAGING PRODUCED ON SITE. G.C. TO COORDINATE LOCATION WITH BASE BUILDING CONTRACTOR.
5. ALL SWITCHES, RECEPTACLES, AND COVER PLATES IN PUBLIC AREAS SHALL BE BLACK.
6. CONTRACTOR SHALL VERIFY ALL ROUGH-IN MECHANICAL AND ELECTRICAL REQUIREMENTS FOR ALL EQUIPMENT WITH OWNER'S FOOD SERVICE EQUIPMENT CONSULTANT.
7. AT ALL PLATFORM BOOTH LOCATIONS, INSTALL PERMANENT TABLE PLACARDS STATING "PLEASE WATCH YOUR STEP" AS PROVIDED BY OWNER.
8. WALL-MOUNTED EQUIPMENT SHALL BE SEALED AT WALL. FLOOR MOUNTED EQUIPMENT SHALL BE SEALED TO FLOOR OR ELEVATED ON 6" H. CLEARANCE LEGS. COUNTER-MOUNTED FIXED EQUIPMENT SHALL BE SEALED W/ NON-TOXIC SEALANT OR ELEVATED ON 4" H. CLEARANCE LEGS. FOOD / UTENSIL STORAGE SHELVES SHALL PROVIDE MINIMUM 6" H. CLEARANCE FROM FLOOR.
9. G.C. SHALL PROVIDE SOLID FRT WOOD OR SHEET METAL BLOCKING FOR OWNER-PROVIDED A/V EQUIPMENT.

EQUIP. SCHED. NOTES

1. SEE SHEET A3.2 FOR EQUIPMENT SCHEDULE. THE QUANTITIES LISTED THEREIN ARE INFORMATIONAL ONLY AND DO NOT RELIEVE THE CONTRACTORS OR VENDORS FROM PROVIDING ALL REQUIRED ITEMS SHOWN IN THE DRAWINGS.
2. G.C. TO FIELD VERIFY THE CONDITION ALL EXISTING EQUIPMENT AND FIXTURES TO BE RELOCATED PRIOR TO BID. PROVIDE ITEMIZED ALTERNATE PRICING FOR NEW EQUIPMENT/ FIXTURES TO REPLACE THE DAMAGED OR INSUFFICIENT EXISTING EQUIPMENT.
3. SEE MEP DRAWINGS FOR WALK-IN / ICE MACHINE CONDENSING UNITS & EXHAUST FANS.
4. DO NOT SCALE DRAWINGS. COORDINATE EQUIPMENT LOCATIONS IN FIELD WITH MILLWORK. VERIFY CURRENT EQUIPMENT CUT SHEETS W/ EQUIPMENT VENDOR. VERIFY EQUIPMENT REQUIREMENTS INCLUDING WATER, DRAIN POWER, OUTLET LOCATIONS/HEIGHTS, ETC.

P.O.S. / PRINTER SCHEDULE

DESCRIPTION
CA1 INSTALL (1) CAT5E HOMERUN TO OFFICE, (1) PRINTER, (1) SINGLE ORANGE ELEC. OUTLET
CA6 INSTALL (3) CAT5E HOMERUNS TO OFFICE, (1) CASH DRAWER, (1) TERMINAL, (1) TEL. OUTLET, (1) DUPLEX ORANGE ELEC. OUTLET
CA12 IN OFFICE INSTALL AS FOLLOWS: - FRT PLYWOOD BACKBOARD WITH RACK MOUNTED 48 PORT PATCH PANEL - (1) QUAD ORANGE OUTLET UNDER DESK BENEATH PLYWOOD AREA - (1) QUAD ORANGE OUTLET UP HIGH ON PLYWOOD BACKBOARD - (1) QUAD REGULAR OUTLET UNDER DESK AWAY FROM ORANGE OUTLET - (3) CAT 5E HOMERUNS TO OFFICE PATCH PANEL FROM BUILDING'S DMARC ROOM FOR PHONE AND DATA EXTENSION

POS CALCULATIONS		
AREA SERVED	CALCULATION	# OF POS REQ'D
INTERIOR BAR:	2 (FIX. QTY.)	2 POS
BAR:	$253 - 36$	
INT. SEATS:	217	
(MINUS) BAR SEATS:	$217/50 = 4.34$	5 POS
TOTAL:		7 POS

P.O.S. / PRINTER NOTES

1. UNLESS NOTED OTHERWISE AT EACH P.O.S. LOCATION, PROVIDE (2) CAT6 HOMERUNS AND DEDICATED DUAL ORANGE ELECTRICAL RECEPTACLE. PROVIDE (1) CAT6 AT EACH PRINTER.
2. RUN (3) CAT6 HOMERUNS FROM BUILDING DMARC TO PHONE SYSTEM LOCATION IN OFFICE (V.I.F.)
3. AT PRINTERS ALONG EXPO LINE: PROVIDE DEDICATED SINGLE ORANGE ELECTRICAL RECEPTACLE AND (1) CAT6 HOMERUN - BOTH ON SERVER SIDE
4. SEE ELECTRICAL DRAWINGS FOR OUTLET AND DATA RECEPTACLES PROVIDED FOR HOST STAND.
5. RUN ALL CAT6 HOMERUNS TO OFFICE (V.I.F.)

EQUIPMENT PLAN KEYNOTES

- | | |
|---|--|
| <ol style="list-style-type: none"> 1 WALL BLOCKING AS REQ'D. (TYP.) - SEE NOTE 3 (THIS SHT.) & ELEVATIONS SHT. A6.2 2 PRINTER STATION - SEE ELEC. DWGS. (TYP.) & ELEVATIONS ON SHT. A6.2 3 A/V - SEE ELEC. DWGS. 4 60" H. S.S. CORNER GUARDS (TYP.) 5 INSTALL ELEC. OUTLET & CAT 5E OUTLET - SEE ELEC. DWGS. 6 (NOT USED) 7 SEE ELECTRICAL DWGS. FOR OFFICE ELECTRICAL REQUIREMENTS 8 INSTALL DUPLEX OUTLET W/ USB PORT @ 8'-0" O.C. ON DIE WALL PUBLIC SIDE AS HIGH AS POSSIBLE & CENTERED HORIZ. IN MILLWORK PANEL - SEE ELEC. DWGS. & BAR ELEV. SHT. A8 9 INTERNALLY LIT LIQUOR STEPS - SEE SHT. A9 11 11A. POS STATION - SEE ELEC. DWGS. (TYP.) - SEE DETAIL 1004 FOR WALL-MNTD. TOUCH SCREEN & SHELF - BAR POS STATIONS ON WIRE SHELVES AS SHOWN 11B. MAINTAIN CLEAR SPACE @ POS STATION AS SHOWN 12 INSTALL ADD'L. ELEC. OUTLET FOR OWNER FUTURE EQUIP. - VERIFY REQMTS. W/ OWNER IN FIELD | <ol style="list-style-type: none"> 13 HOST LOCATION - SEE ELEC. 14 MUSIC LOCATION - SEE ELEC. 15 WALL-MOUNTED COAT HOOK LOCATION FOR EMPLOYEE STORAGE 16 RECESSED HOSE BIB - SEE PLUMBING DWGS. 17 NEW VENTLESS GAS FIREPLACE - SEE SHEET A10.1 18 EXTEND BAR FLOORING BEYOND COCKTAIL STATION - SEE A5.101 19 UNDER-CABINET PLUG-IN LIGHT - SEE A301 20 SEE ENLARGED DETAIL ON SHT. A9 FOR EXTENDED BLKG. FOR SODA GUN HOLSTER SUPPORT (TYP. @ EA. SODA GUN LOC. @ BAR) 21 RUN GAS LINE UNDER PATIO PAVER SYS. TO FIRE FEATURE - SEE PLUMB. DRAWINGS. 22 23 STAINED SOLID MAPLE WD. CABINET DOOR. 24 25 WALK-IN COOLER CONDENSER MOUNTED ABOVE COOLER - SEE SHT. AEB |
|---|--|

BID ALTERNATE #22

PROVIDE BID ALTERNATE PRICING FOR INSTALLING GAS LINE TO FIRE PIT ABOVE GROUND ALONG RAILING IN LIEU OF TRENCHING EXISTING CONCRETE PATIO SLAB

REASON					
ISSUE DESCRIPTION	ISSUED FOR ENGINEERING	ISSUED FOR BID, PERMIT, & LL REVIEW			
ISSUE DATE	19 FEB 16	08 MAR 16			
PREPARED FOR:					
BL RESTAURANT OPERATIONS, LLC ADDISON PARK PLACE, 4550 BELTWAY DRIVE, ADDISON, TX 75001					
RESTAURANT & BAR					
FOUNDRY ROW 10100 FORTSETTLERS BLVD DALLAS, TEXAS 75243					
PROFESSIONAL SEAL:					
SHEET NUMBER:					
A4 OF 23					
<small>© 2016, BARKER NESTOR, INC. ALL RIGHTS RESERVED</small>					